(*b*) That he agrees to make the fellings in a methodical manner from one corner of the coupe to the other, leaving the standard trees marked on the area intact along with all trees less than 9" in girth and trees yielding minor forest produce and such of the straight growing poles of the reserved kinds as are left out unmarked as standards through an oversight and all trees, shrubs and other thorny growth that are coming up within a radius of 6 feet from the sandal trees and saplings.

(*c*) That if any standard tree or other trees and saplings to be preserved on the area are cut, he will pay a fine not exceeding Rs. 5 per tree.

(*d*) That he agrees to remove all the charcoal outside the forest limits before the 30th June 1930 and that each removal shall be covered by a passport issued by the Range Officer or any other officer deputed by the District Forest Officer in this behalf after check and measurement.

(*e*) That he agrees to abide by the rules of the department as regards the kindling of fires and holds himself responsible for any forest offences committed by his agents, employees or workmen.

(*f*) That he agrees that no operations shall take place in the forest after sunset and before sunrise.

(*g*) That he agrees to the cancellation of the contract and the forfeiture of the deposit for breach of any of the terms of the contract.

(*h*) That he realizes that the contract lasts up to 30th June 1930 and that after which date he can have no right whatsoever over the coupe and the charcoal paid left unremoved.

(*i*) That he agrees not to sub-let the contract to anybody unless with the written sanction of the District Forest Officer.

MOHOMED PIR,
District Forest Officer.

BHADRAVATI DIVISION.

Abstract Notification dated 22nd January 1930.

The attention of the public is invited to the detailed notification, dated 22nd January 1930, published on pages 114 and 115 Part VI of the *Mysore Gazette*, dated 30th January 1930, regarding the sale of standing timber trees in the Forest of Channagiri Range, of the Bhadravati Division, for the year ending 30th June 1930.

Date of sale 17th February 1930.

C. H. EAGLES,
District Forest Officer.

SAGAR FOREST DIVISION.

Abstract Notification dated 25th January 1930.

The attention of the public is invited to the notification published on pages 115 and 116 Part VI of the *Mysore Gazette*, dated 30th January 1930, regarding the auction sale of timber in the several Depots of the Division between the 17th February 1930 to 18th March 1930.

B. MADHAVA RAO,
District Forest Officer.

ENGINEERING DEPARTMENT.

SPECIAL WATER SUPPLY CONSTRUCTION DIVISION.

Dated 28th January 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Sanitary and Town Planning Division, up to 2 P.M. of 17th February 1930, for construction of flushing latrines for servants at Government House, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the construction of the two latrines for servants at Government House, Mysore," a default of which tenders will be rejected. Tenders paying the earnest money in cash should credit the amount at the State Huzur Treasury obtaining credit as written up in the office and enclose duplicate treasury receipt along with the tender.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money in rejected tenders will be returned.

9. Charges on account of setting out works, scaffolding materials, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately; but should be borne entirely by the contractor.

10. Rates for lumpsum items in the sanctioned estimates and for items for which there is no provision in the estimate shall be those that will be fixed by the Executive Engineer either as per schedule of rates prevailing in the market or as per data worked out with not more than 10 per cent for contractor's profit.

Abstract.

Sl. No.	Items of work	Unit	Quantity
	(A) Servants' Latrine with 8 seated Delhi Range Closets at the Servants' Block.		
	I. Latrine Building.—		
1	Earthwork excavation for foundation ordinary soil ...	Cyds.	17
2	Concrete with chunam mortar and stone jelly ...	C.ft.	109
3	Burnt brick in chunam mortar masonry	"	918
4	Roofing with reinforced concrete 4" thick	S.ft.	94
5	Plastering with chunam mortar rough cast smooth chunam plaster border all round as per plan.	Sqr.	8·56
6	Cement plastering ½ thick with (1 to 3) cement and sand	"	8·75
7	9" cornice with brick in chunam mortar and plastering, etc., complete.	R.ft.	56·5
8	Ornamental parapet wall with brick in chunam mortar and complete with plasters as per design.	"	54·5
9	Flooring with ½" cement plaster and marking tiles including sunki concrete bed of 4" thickness.	Sqr.	6.3
10	Teakwood doors with panelled shutters complete with hinges, bolts and door handles of approved design and fixing.	S.ft.	90
11	Reinforced concrete ventilators of approved design ...	"	12
12	Burnt stone slab roughly dressed 6" thick ...	"	33
13	White and colour washing 3 coats	Sqr.	3·4
14	Teakwood battened shutters complete with bolts and plugs and fixing to private closet compartments.	S.ft.	88
15	Painting chocolate and cream coats to doors and shutters ...	Sqr.	1·78
16	Dismantling the existing mud sheet latrine and removing the platform, carrying rubbish and clearing the ground and carting all removed materials to stores.	No.	1
	II. Fixing Sanitary Fittings.—		
	Fixing the range of 8 number 'Delhi' range closets with flushing tank, stoneware channels of soil pipe drain with flush pipe connections to each closet complete upto first manhole.	No.	1

Detailed estimate of Ryots share of work to be done to Manchenahalli Tank, Regd. No. 69 of Goribidnur Taluk.

No.	Items of work	Per	Quantity
1	Earthwork to bund watering and Tamping with lead, lift, etc. complete.	C.yds.	9,555
2	Turfing	S.yds.	18,233
	Total ...	..	...
	Contingency at 5 per cent ...	...	...
	Grand total Rs. ...	...	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

SHIMOGA DIVISION.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 15th February 1930, for Restoring Varada Voddu near Yelagalale Regd. No. 896 Sagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May of 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Varada Voddu near Yelagalale Regd. No. 896, Sagar Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate for restoring Varada Voddu near Yelagalale Reg. No. 896, Sagar Taluk, Shimoga District.

Sl. No.	Items of work	Per	Quantity
1	Jungle clearing etc., over the channel and training bank ...	Lump	sum
2	Dismantling old masonry including removing ...	C.ft.	1,127
3	Earthwork to band including consolidation	C.yds.	1,017
4	Earthwork excavating foundation	,,	144
5	Surki mortar concrete	C.ft.	637
6	Black stone new in surki mortar	,,	3,723
	do old do	,,	563
7	Deep cement pointing	Sqr.	15·57
8	Providing burnt stone slabs dressed and fixed	S.ft.	98
9	Providing Teakwood shutter for Head sluice 2½" thick	,,	4
10	Cutting grovers for slabs for shutter	R.ft.	8
11	Do for top guiding slab (2½' x 3" x 3") ..	each	1
12	New rough stone work	C.yd.	109
13	Rough stone jelley filling	,,	72
14	Old rough stone work with new jelly	,,	30
15	Clearing silt in channel	Lump	sum
16	Turfing banks	,,	,,
17	Earthwork side cutting of river bank	,,	,,
18	Providing gearing arrangements, etc., as per details of the estimate.	,,	,,
19	Other unforeseen items and baling, etc	,,	,,